

**CITY OF CHESTER**

**Chester Fire Department Administration Building Floor Cover Replacement (Station 1)**

BID

Proposal of \_\_\_\_\_ hereinafter called "Bidder", organized and existing under the laws of the State of \_\_\_\_\_ doing business as a \_\_\_\_\_.

To the City of Chester (hereinafter called "Owner"). In compliance with your Advertisement for Bids, bidder hereby proposes to perform all work on Chester Fire Department Administration Building Floor Cover Replacement (Station 1) in strict accordance with the Contract Documents, within the time set forth therein, and at the prices stated below.

By submission of this Bid, each Bidder certifies, and in the case of a joint Bid each party thereto certifies as to this organization, that this Bid has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this Bid with any other Bidder or with any competitor.

Bidder hereby agrees to commence Work under this Contract on or before a date to be specified in the Notice to Proceed and to fully complete the Project within 30 consecutive calendar days.

BIDDER acknowledges receipt of the following Addendum:

---

---

**SCOPE OF WORK**

## Chester Fire Department Emergency Generator (Station 1)

Scope of the work: Materials and Labor for existing building roof repairs, damaged roof insulation replacement and wall insulation repair with protection for engine room exposed wall insulation.

1. Remove approximately 1,850 square feet of existing vinyl floor tile and carpeting. Removal will need to be coordinated with Chester Fire Chief on a room-to-room basis, to have furniture relocated for work to be completed while other areas are in use.
2. Replace existing flooring with Aladdin Commercial 20 mil LVT glue planks as follows:

1) Lobby and Hall area	Approximately 440 sf	type <u>872</u>
2) Lobby Rest Room	Approximately 56 sf	type <u>872</u>
3) Office 101	Approximately 224 sf	type <u>1714</u>
4) Conference Room	Approximately 425 sf	type <u>872</u>
5) Office 102	Approximately 208 sf	type <u>4913</u>
6) Hall Closet	Approximately 32 sf	type <u>872</u>
7) Office Rest Room	Approximately 88 sf	type <u>4913</u>
8) Supply Room	Approximately 90 sf	type <u>9411</u>
9) Break Room	Approximately 45 sf	type <u>9411</u>
10) Office 104	Approximately 272 sf	type <u>4913</u>
3. Remove and install approximately 545 feet of new 4" Cove Base \_\_\_\_ color \_\_\_\_\_
4. Removal and installation will need to be coordinated with Chester Fire Chief on a room-to-room basis, to have furniture relocated for work to be completed while other areas are in use.

PROPOSED CONTRACTOR: The Contractor shall not draw up an Agreement with any subcontractor or permit any subcontractor to perform any work included in this Contract.

### BID CERTIFICATION

\_\_\_\_\_  
WITNESS

FIRM: \_\_\_\_\_

BY: \_\_\_\_\_

TITLE: \_\_\_\_\_

DATE: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

\_\_\_\_\_  
PHONE NO. \_\_\_\_\_